

Ramp Slope will vary

Valve box must be flush on high side of ramp

Water Main and Service Valve Box Adjustments (replacement lid and/or valve box sections will be supplied by the City)

Contractor must insure that no construction debris remains inside valve box and valve is accessible

Locate truncated domes/ramp centers so that valve boxes do not fall within the dome area, if possible

